THIRD ANGLE PROJECTION DIMENSIONS IN mm DO NOT SCALE





VIEW ON ARROW A
(REAR PANEL DETAILS)



TERMINAL CONNECTIONS:



OPTION TERMINALS (WHEN OPTION FITTED):



INSTALLATION:

1 INSERT UNIT INTO PANEL CUTOUT FROM FRONT.

2 SCREW CLAMPS ARE CLIPPED TO THE INDICATOR & TIGHTENED FROM REAR OF PANEL. RECOMMENDED TORQUE 22cNm MAX.

3 FOR PANELS GREATER THAN 3mm THICK ADD ADDITIONAL DEPTH FOR CLAMPS. (ie ADD PANEL THICKNESS LESS 3mm)

PANEL CUTOUT:

DIN 43 700: $138^{+1.0}_{-0}$ x $68^{+0.7}_{-0}$

FOR IP66: $136^{+0.5}_{-0}$ x $66.2^{+0.5}_{-0}$

Iss.	Date	Modification	Ckd.	Appd.
1	23.05.2017	.		

BEKA associates Hitchin England
company confidential, copyright reserved.

Title: CUSTOMER DRAWING for BA378E 2 INPUT TIMER IN PANEL MOUNTING ENCLOSURE

Drawn	Checked	Scale
RC	.	NTS

Drawing No. CD378E